

- GENERAL ELECTRICAL SPECIFICATIONS

1.

THE ELECTRICAL CONTRACTOR IS RESPONSIBLE FOR A NEAT "WORKMAN-LIKE" ELECTRICAL INSTALLATION THAT IS COMPLETE IN EVERY RESPECT. BY ACT OF SUBMITTING A BID FOR THE PROPOSED WORK, THIS CONTRACTOR AGREES TO PROVIDE ALL LABOR, TOOLS, EQUIPMENT AND APPROVED MATERIAL NECESSARY TO PROVIDE THE OWNER A SERVICEABLE AND COMPLETE SYSTEM AS INDICATED WITHIN THE SCOPE OF THESE PLANS AND SPECIFICATIONS.

2.

THE ENTIRE ELECTRICAL SYSTEM SHALL BE INSTALLED IN STRICT ACCORDANCE WITH THE STANDARD ELECTRICAL CODE PROVISIONS AND LOCAL REGULATIONS OR CODES HAVING JURISDICTION. THE PLANS AND SPECIFICATIONS CONTAINED WITHIN THIS SET OF CONSTRUCTION DOCUMENTS ARE INTENDED TO ILLUSTRATE THE SCOPE OF WORK REQUIRED FOR A ELECTRICAL INSTALLATION ONLY, THE INFORMATION SHOWN SHALL IN NO WAY SUPERCEDE THE CODE PROVISIONS OR IN ANY WAY GIVE PERMISSION TO THE ELECTRICAL CONTRACTOR TO INSTALL A SYSTEM FOUND TO BE IN NON-COMPLIANCE.

3.

THIS CONTRACTOR SHALL REVIEW THE ENTIRE SET OF CONSTRUCTION DOCUMENTS FOR AREAS OF WORK THAT DIRECTLY AFFECT THE ELECTRICAL DESIGN, INSTALLATION METHODS, FIRE STOPPING, PATCHING REQUIREMENTS, SPECIAL INSTALLATION REQUIRE-GENERAL LAYOUTS, DETAILS AND SCHEDULING OF ACTUAL INSTALLATION. AND SCHEMATICS NECESSARY TO PERFORM A COMPLETE, SERVICEABLE JOB, EVEN IF NOT EXPRESSLY SHOWN) SHALL, BY ACT OF SUBMITTING A BID, BE UNDERSTOOD TO BE A PART OF THIS BID, QUESTIONS OR CLARIFICATIONS WHICH NEED TO BE ADDRESSED SHALL BE DONE PRIOR TO BIDDING OR SIGNING ANY FORM OF CONTRACT FOR THE RESPECTIVE WORK. NO ALLOWANCE SHALL BE MADE FOR ITEMS UNDERSTOOD TO BE A REASONABLE PART OF THIS WORK AFTER SUCH CONTRACT IS SIGNED.

4.

THE ELECTRICAL CONTRACTOR IS RESPONSIBLE FOR THE COORDINATION OF WORK WITH OTHER TRADES. IT IS REQUIRED BY CONTRACT FOR THE ELECTRICAL CONTRACTOR TO ATTEND PROGRESS MEETINGS AND AT ALL TIMES TO KEEP THE JOBSITE SUPER-INTENDENT OR PROJECT MANAGER INFORMED OF ANY SCHEDULE DELAYS AND APPARENT CAUSES AND THE REMEDIAL ACTION TO BE TAKEN TO ACCOMPLISH THE COMPLETED PROJECT ACCORDING TO SCHEDULE. THIS CONTRACTOR AGREES TO TAKE NECESSARY STEPS TO KEEP HIS WORK IN CONTROL, INSPECTED AND FINISHED IN A TIMELY MANNER AS TO NOT HOLD UP OTHER TRADES WORK AND THERE-BY THE ENTIRE PROJECT'S TIMELY COMPLETION.

5.

THE ELECTRICAL CONTRACTOR SHALL OBTAIN AND PAY FOR ALL REQUIRED PERMITS, BONDS AND OTHER NECESSARY LICENSES OR APPLICATIONS AS REQUIRED BY THE LOCAL AND STATE BUILDING DEPARTMENTS. THE CONTRACTOR SHALL CALL FOR ALL NECESSARY INSPECTIONS AND PERFORM SAME IN ACCORDANCE WITH THE LOCAL REQUIREMENTS. THIS CONTRACTOR SHALL NOT ALLOW ANY PORTION OF HIS WORK TO BE COVERED OR CONCEALED PRIOR TO REQUIRED INSPECTIONS AND WRITTEN NOTICE OF APPROVAL.

6.

THIS CONTRACTOR IS REQUIRED TO MAINTAIN A MANUAL ON SITE CONTAINING THE REQUIRED MSDS SHEETS FOR PRODUCTS, CLEANERS AND OTHER MATERIALS USED ON THIS PROJECT. THE INFORMATION MAY BE GIVEN TO THE JOBSITE OFFICE FOR RECORDS AND REVIEW. THIS CONTRACTOR SHALL FURNISH TO THE JOBSITE SUPER-INTENDENT THE NAME OF HIS APPOINTED SAFETY OFFICER AND PHONE NUMBER FOR USE IN THE EVENT OF AN EMERGENCY.

7.

THE ELECTRIC EQUIPMENT SCHEDULES SHOWN ON THE PLAN ARE INTENDED TO ESTABLISH THE TYPE AND QUALITY OF EQUIPMENT REQUESTED BY THE OWNER AND ENGINEER, EQUALS MAY BE USED IF BID AS A VOLUNTARY ALTERNATE. THIS CONTRACTOR IS REQUIRED TO MEET THE ESTABLISHED QUALITY IN ANY CASE, AND WILL BE REQUIRED TO PROVIDE SAME IF THE MATERIAL THEY USED IN THEIR PROPOSAL WAS NOT APPROVED PRIOR TO BIDDING OR IS VIEWED AFTER THE BIDDING NOT TO MEET THE QUALITY REQUIREMENT. IT IS THIS CONTRACTORS' RESPONSIBILITY TO OBTAIN THE APPROVAL PRIOR TO BID OR RISK IF NOT APPROVED AFTERWARD.

8.

THIS CONTRACTOR IS RESPONSIBLE FOR DAILY CLEAN-UP OF HIS DEBRIS AND MATERIAL. ORGANIZATION TO KEEP THE JOB SITE NEAT IN APPEARANCE. SHOULD THIS CONTRACTOR FAIL TO KEEP HIS TRADES WORK CLEAN FROM DEBRIS ACCUMULATION, THE JOB SITE SUPERINTENDENT WILL SEE THAT A FIRM OR PERSON WILL PERFORM THE CLEAN-UP AND HAVE THE EXPENSE BACK-CHARGED AGAINST THIS CONTRACTORS CONTRACT.

9.

THE ELECTRICAL CONTRACTOR SHALL COORDINATE EQUIPMENT CONNECTION WITH THE CONTRACTOR PROVIDING SAME TO INSURE A PROPER AND COMPLETE INSTALLATION OF EACH PIECE OF EQUIPMENT AND TO MEET THE OVERALL SYSTEM REQUIREMENTS.

10.

THERMOSTATS FOR HEATING AND AIR-CONDITIONING EQUIPMENT TO BE FURNISHED BY THE H.V.A.C. CONTRACTOR. THE ELECTRICAL CONTRACTOR SHALL RUN THE CONTROL WIRING FROM THE THERMOSTAT TO THE EQUIPMENT, AND IS RESPONSIBLE FOR VERIFYING THE PROPER INSTALLATION AND FOR THE FINAL CONNECTION TO THE MECHANICAL EQUIPMENT.

11.

ALL EXHALST FANS ARE TO BE FURNISHED AND INSTALLED BY THE MECH. CONTRACTOR, THIS SHALL INCLUDE DUCTING PER DUCTING TO THE EXTERIOR OF THE BUILDING. THE ELECTRICAL CONTRACTOR SHALL SUPPLY WIRING AND CONNECT TO THE EXHAUST UNITS ONLY.

- GENERAL ELECTRICAL NOTES:

• ALL BUILDING REQUIREMENTS TO FOLLOW SPECIFICATIONS PER HILTON LATEST STANDARDS FOR HOME 2.

• CONTRACTOR MUST MAKE THEIR COMPANY FAMILIAR WITH THOSE STANDARDS SET FORTH BY HILTON.

• ALL DRAWINGS SUBJECT TO CHANGE IF DRAWINGS CONFLICT WITH HILTON STANDARDS.

1. PROPERTIES W/ 360 KEYS OR MORE MUST ADD A MATV RACK.

2. PROPERTIES W/ 150 KEYS OR MORE MUST ADD A PHONE RACK.

3. FLOOR MOUNTED 1 9" RACK MUST BE PROVIDED BY OWNER AND INSTALLED PRIOR TO ONG INSTALLATION.

4. ONG EQUIPMENT AT WORKSTATIONS (INCLUDING FRONT DESK) MUST BE WITHIN 300' OF THE COMPUTER ROOM (PBX).

5. INTERFACE OF SYSTEMS (PHONE/MATV/POINT OF SALE) WITH SERIAL CABLE MUST BE WITHIN 100' OF THE ONG EQUIPMENT IN THE COMPUTER ROOM. LARGER DISTANCES WILL REQUIRE FIBEROPTICS IN LIEU OF CAT6 CABLE.

6. 8'-6" MINIMUM CEILING HEIGHT IN COMPUTERS.

• OWNER MUST VERIFY REQUIREMENTS WITH EQUIPMENT PROVIDERS PRIOR TO CONSTRUCTION FOR VERIFICATION THAT THE EQUIPMENT WILL FIT.

• CONTACT MATV PROVIDER (SUCH AS LODGENET) DIRECTLY FOR SPACE REQUIREMENTS INCLUDING WIRING RECOMMENDATIONS.

• ALL WIRING TO BE SIZED PER 2017 NEC

NOTE: SEE HOME 2 BUILDING AND FURNISHING SPECIFICATION MANUAL FOR ALL ELECTRICAL REQUIREMENTS

• ANY ITEM REQUIRING AN ELECTRICAL RECEIPT OR HARDWIRE CONNECTION THAT IS DEPICTED GRAPHICALLY OR WRITTEN ON THE CONSTRUCTION DOCUMENTS, THAT CONNECTION IS THE RESPONSIBILITY OF THE ELECTRICAL CONTRACTOR.

• NOT ALL CIRCUITS MAY BE DEPICTED ON THE DRAWINGS OR PANEL SCHEDULES. EXTRA CIRCUIT BREAKERS HAVE BEEN PROVIDED IN THE PANELS FOR USE AS REQUIRED. IF THE ELECTRICAL CONTRACTOR IS AWARE OF A CIRCUIT BREAKER THAT IS NEEDED AND IS NOT ON THE DRAWINGS IT IS THEIR RESPONSIBILITY TO PROVIDE ALL BREAKERS REQUIRED FOR THE JOB TO BE COMPLETED.

NOTE ALL TECHNOLOGY WIRING SYSTEMS MUST BE SUPPLIED & INSTALLED BY A SUPPLIER APPROVED BY HILTON WHO IS A PAINDUIT CERTIFIED INSTALLER (PCI) PARTNER. REF. 2518 FOR ADDITIONAL INFORMATION.
- ELECTRICAL REQUIREMENTS:

1. HEIGHT OF ALL SWITCHES, OUTLETS, ETC., TO MEET A.D.A. REQUIREMENTS AND/OR LOCAL CODES.

2. COLOR OF ALL ELECTRICAL DEVICES AND COVERS PLATES TO BE IVORY.

3. ALL OUTLETS TO BE DEDICATED 20A, U.N.O.

4. PHONE LINES TO BE DEDICATED (DIRECT DIAL) W/R 110 JACK.

5. EACH ADDITIONAL MATV RACK REQUIRES AN ADDITIONAL 15A, TWIST LOCK (BASED ON LODGENET REQUIREMENTS).

6. PBX EQUIPMENT ROOM TEMPERATURE TO REMAIN 60 TO 75 DEGREES F, YEAR ROUND FOR MATV EQUIPMENT, LODGENET RACK HEAT OUTPUT CALCULATION: (UP TO 600 KEYS) 3000+ 10 x (# OF ROOMS) = TOTAL BTUS.

ELECTRICAL NOTES:

• ALL SYSTEMS MUST MEET ALL LOCAL AND STATE CODES. CONTRACTOR IS TO VERIFY UPDATED CODES.

• ALL FIXTURES SHOWN HALF SHADED OR WITH 'E' SUFFIX SHALL BE INSTALLED UTILIZING AN EMERGENCY DEVICE.

• ALL FIXTURES WITH 'O' SUFFIX OR CONNECTED TO A MOTION SENSOR SHALL HAVE PROGRAMMABLE BALLAST.

• ALL FIXTURES SHOWN WITH 'F' SHALL HAVE A FLANGED TRIM.

• PROVIDE FOUR 4" CONDUITS TO STREET FOR DATA, TELEPHONE, AND TV SERVICES WITH ONE SPARE. COORDINATE EXACT SERVICE REQUIREMENTS WITH LOCAL SUPPLIER. (CONDUITS MAY TERMINATE FIVE FEET OUTSIDE OF BUILDING FOOTPRINT IF DIRECT BURY IS ALLOWED BY LOCAL SUPPLIERS)

• PROVIDE 1" EMPTY CONDUIT TO PANEL FOR LANDSCAPE LIGHTING. SUPPLY POWER TO TYPICAL SECURITY SYSTEMS PROVISIONS, INCLUDING DOOR SENSORS AND ALARMS ARE EXPECTED.

ELEVATOR EQUIPMENT NOTES:

ELEVATOR AND ASSOCIATED EQUIPMENT SHALL BE INSTALLED IN ACCORDANCE WITH LATEST ENFORCED EDITION OF NEC ARTICLE 600 AND ANSI/ASME A17.1

1. PROVIDE TWO 20A 1 POLE BREAKERS IN PANEL FOR THE LIGHTS AND RECEPTS IN THE ELEVATOR EQUIPMENT ROOM AND PIT. THE PIT LIGHTING SHALL NOT BE CONNECTED TO THE LOAD SIDE OF THE GFI RECEPT.

2. PROVIDE TWO 20A 1POLE BREAKERS FOR THE CAR LIGHTS, FAN AND THE HEAT EXCHANGER CIRCUITS. ONE 15A 1 POLE BREAKER FOR THE APE SYSTEM. FURNISH A DISCONNECT SWITCH CAPABLE OF BEING LOCKED IN THE OPEN POSITION. FURNISH AN ENGRAVED LABEL TO READ 'SUPPLY CIRCUITS FROM PANEL'

3. PROVIDE A DISCONNECT SWITCH LOCKABLE IN THE OPEN POSITION AND WITH DUAL ELEMENT 150A FUSES WITH NEUTRAL KIT AND A GROUND KIT

4. PROVIDE ENGRAVED LABELS AT ALL DISCONNECTS SWITCHES IN THE ELEVATOR EQUIPMENT ROOM READING 'WARNING - PARTS OF THE CONTROLLER ARE NOT DE-ENERGIZED BY THIS SWITCH'

5. FIRE ALARM SYSTEM FOR ELEVATOR BY ELEVATOR SUPPLIER.

POOL ELECTRICAL NOTES:

1. ALL ELECTRICAL POWER FOR POOL AREA IS TO BE RAN TO THE POOL PANEL BOX.

2. ALL POOL FIXTURES ARE TO BE WATERPROOF AND GFI PROTECTED

3. PROVIDE CONDUIT TO THE UNDER GROUND POOL LIGHTS

4. ELECTRICAL CONTRACTOR TO COORDINATE WITH POOL DRAWINGS AND SPECIFICATION DONE BY OTHERS AND POOL CONTRACTORS APPROVED SHOP DRAWINGS FOR ALL ELECTRICAL REQUIREMENTS FOR LIGHT, POWER AND/OR EQUIPMENT

ELECTRICAL NOTES:

1. GUEST LAUNDRY OUTLETS BEHIND THE WASHERS AND DRYERS MUST BE LOCATED BELOW THE TOP OF THE UNITS AND MUST BE CONCEALED FROM THE GUESTS VIEW

2. BACK-TO-BACK THRU-WALL OUTLETS ARE NOT PERMITTED. GUESTROOM POWER OUTLETS, TELEPHONE OUTLETS, TELEVISION OUTLETS, HVAC BOXES, ECT MUST BE OFFSET.

3. PROVIDE A COMPLETE POINT ADDRESSABLE SMOKE DETECTION AND ANNUNCIATION SYSTEM THROUGHOUT ALL AREAS OF THE HOTEL. OTHER THAN GUEST ROOMS/SUITES, THE PROPERTY MUST HAVE SYSTEM-CONNECTED, HARD WIRED SMOKE DETECTORS. ADDRESSABLE SMOKE DETECTORS MUST BE PROVIDED WITHIN MECHANICAL ROOMS/ELECTRICAL ROOMS, ELEVATOR/LIFT MACHINE ROOMS AND EQUIPMENT/UTILITY ROOMS, COMPUTER/TELECOM/PBX ROOMS, STORAGE ROOMS (OVER 35 FT)

4. PROVIDE A DEDICATED PANIC BUTTON IN CASH HANDLING AREAS, AREAS OF POTENTIAL GAS RELEASE AND AT EACH STATION AT THE FRONT DESK

5. ALL GROUND EQUIPMENT TO BE SCREENED FOR VIEW

6. IF HOTEL ISP CIRCUIT PROVIDER CANNOT DELIVER THE FIBER DATA CIRCUIT IN TIME FOR THE HOTEL'S OPENING, THEN TV CABLE CAN BE TEMPORARILY USED UNTIL FIBER INSTALLATION IS COMPLETED IF:

A. HOTEL MUST HAVE A CONTRACTED FIBER CIRCUIT

B. TV CABLE USED MUST BE A BUSINESS CLASS CABLE OF APPROPRIATE SIZE

7. GUESTROOM HVAC AND LIGHTING TO BE CONTROLLED WITH A PASSIVE INFRARED OCCUPANCY SENSOR WITH WIRELESS INTERFACE TO THE ROOM AUTOMATION SYSTEM. EXAMPLE VENDORS - INNOCOM, VERDANT & TELKOMET - EACH HAVE THERMOSTATS WITH OCCUPANCY SENSORS AS WELL AS REMOTE OCCUPANCY SENSORS THAT CONTROL LIGHTING.

8. ALL GUESTROOM PTAC UNITS MUST HAVE A HARDWIRED SUB-BASE DISCONNECT.

9. CARBON MONOXIDE DETECTORS ARE REQUIRED IN THE ROOM OR AREA OF ORIGIN FOR ALL FUEL-FIRED EQUIPMENT, INCLUDING, BUT NOT LIMITED TO: DRYERS, WATER HEATERS, POOL HEATERS, FURNACES, ETC.

GENERAL NOTES

ALTHOUGH DRAINAGE ARE DRAWN TO SCALE, THE ACCURACY OF THE DRAWINGS CANNOT BE GUARANTEED. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS OF REPRODUCTION. DIMENSIONS SHALL BE DERIVED FROM DIMENSIONED PLANS.

ALL DIMENSIONS UNLESS OTHERWISE SPECIFIED SHALL BE IN FEET AND INCHES. DIMENSIONS SHALL NOT BE HELD RESPONSIBLE FOR ANY GENERAL CONTRACTOR, FIRST ARCHITECTURAL SERVICES, INC. SHALL BE RESPONSIBLE FOR THE ACCURACY OF THE INFORMATION AND FOR THE INFORMATION BROUGHT TO HER ATTENTION PRIOR TO CONSTRUCTION.

MAUIST ARCHITECTURAL SERVICES, INC.

112 NORTH MAIN STREET
GOSHEN, INDIANA 46526

PHONE: (574) 537-4500
FAX: (574) 537-0808

* Architects
* Planners
* Engineers
* Construction Mgmt.
* Rule 5 and Ms4 Filing

SHEET SIZE 24x36

FT. WAYNE, INDIANA

REVISIONS :

DATE: 05/01/26

JOB NO.: MAS-26-105

NAME:
ELECTRICAL NOTES

SHEET:

E001