

1. ALL SUPPLY, RETURN, AND EXHAUST AIR GRILLES & DIFFUSERS TO BE PROVIDED WITH A BALANCING DAMPER.
2. ALL SUPPLY, RETURN, AND EXHAUST AIR GRILLES & DIFFUSERS TO BE PROVIDED WITH R-6 FOIL BACKED INSULATION.
3. ALL NEW AND EXHAUST AIR GRILLES TO BE PROVIDED WITH AN INSULATED ALUMINUM SQUARE TO ROUND TRANSITION.
4. LOCATIONS OF ALL SUPPLY, RETURN, AND EXHAUST GRILLES & DIFFUSERS TO BE COORDINATED WITH GENERAL, ELECTRICAL, AND FIRE PROTECTION CONTRACTORS PRIOR TO INSTALLATION.

1. ALL DRAINS FOR HVAC UNITS TO BE PRICED WITH A SEP LINE ITEM BY MECHANICAL CONTRACTOR.
2. GAS LINES TO BE PRICED WITH A SEP LINE ITEM BY MECHANICAL CONTRACTOR.

1. THE MECHANICAL CONTRACTOR IS RESPONSIBLE FOR A NEAT "WORKMANLIKE" 1. HEATING-COOLING SYSTEM INSTALLATION THAT IS COMPLETE IN EVERY RESPECT. BY ACT OF SUBMITTING A BID FOR THE PROPOSED WORK, THIS CONTRACTOR AGREES TO PROVIDE ALL LABOR, TOOLS, EQUIPMENT AND APPROVED MATERIAL NECESSARY TO PROVIDE THE OWNER A SERVICEABLE AND COMPLETE SYSTEM AS INDICATED WITHIN THE SCOPE OF THESE PLANS AND SPECIFICATIONS.

2. THE ENTIRE HEATING-COOLING SYSTEM SHALL BE INSTALLED IN STRICT ACCORDANCE WITH THE STANDARD MECHANICAL CODE PROVISIONS AND LOCAL REGULATIONS OR CODES HAVING JURISDICTION. THE PLANS AND SPECIFICATIONS CONTAINED WITHIN THIS SET OF CONSTRUCTION DOCUMENTS ARE INTENDED TO ILLUSTRATE THE SCOPE OF WORK REQUIRED FOR A HEATING AND COOLING INSTALLATION ONLY, THE INFORMATION SHOWN SHALL IN NO WAY SUPERCEDE THE CODE PROVISIONS OR IN ANY WAY GIVE PERMISSION TO THE MECHANICAL CONTRACTOR TO INSTALL A SYSTEM FOUND TO BE IN NON-COMPLIANCE.

3. THIS CONTRACTOR SHALL REVIEW THE ENTIRE SET OF CONSTRUCTION DOCUMENTS FOR AREAS OF WORK THAT DIRECTLY AFFECT THE MECHANICAL DESIGN, INSTALLATION METHODS, FIRE STOPPING, PATCHING REQUIREMENTS, SPECIAL INSULATION REQUIRE-GENERAL LAYOUTS, DETAILS AND SCHEDULING OF ACTUAL INSTALLATION. AND SCHEMATICS NECESSARY TO PERFORM A COMPLETE, SERVICEABLE JOB (EVEN IF NOT EXPRESSLY SHOWN) SHALL, BY ACT OF SUBMITTING A BID, BE UNDERSTOOD TO BE A PART OF THIS BID. QUESTIONS OR CLARIFICATIONS WHICH NEED TO BE ADDRESSED SHALL BE DONE PRIOR TO BIDDING OR SIGNING ANY FORM OF CONTRACT FOR THE RESPECTIVE WORK. NO ALLOWANCE SHALL BE MADE FOR ITEMS UNDERSTOOD TO BE A REASONABLE PART OF THIS WORK AFTER SUCH CONTRACT IS SIGNED. THE MECHANICAL CONTRACTOR IS RESPONSIBLE FOR THE COORDINATION OF WORK.

4. WITH OTHER TRADES, IT IS PROVIDED BY CONTRACT FOR THE MECHANICAL CONTRACTOR ATTEND PROGRESS MEETINGS AND AT ALL TIMES TO KEEP THE JOBSITE SUPER-ATTENDANT OR PROJECT MANAGER INFORMED OF ANY SCHEDULE DELAYS AND APPARENT CAUSES AND THE REMEDIAL ACTION TO BE TAKEN TO ACCOMPLISH THE COMPLETED PROJECT ACCORDING TO SCHEDULE. THIS CONTRACTOR AGREES TO TAKE NECESSARY STEPS TO KEEP HIS WORK IN CONTROL, INSPECTED AND FINISHED IN A TIMELY MANNER AS TO NOT HOLD UP OTHER TRADES WORK AND THERE-BY THE ENTIRE PROJECTS TIMELY COMPLETION.

5. THE H.V.A.C. CONTRACTOR SHALL OBTAIN AND PAY FOR ALL REQUIRED PERMITS, BONDS AND OTHER NECESSARY LICENSES OR EQUIVACAS AS REQUIRED BY THE LOCAL AND STATE BUILDING DEPARTMENTS. THE CONTRACTOR SHALL CALL FOR ALL NECESSARY INSPECTIONS AND PERFORM SAME IN ACCORDANCE WITH THE LOCAL REQUIREMENTS. THIS CONTRACTOR SHALL NOT ALLOW ANY PORTION OF HIS WORK TO BE COVERED OR CONCEALED PRIOR TO REQUIRED INSPECTIONS AND WRITTEN NOTICE OF APPROVAL.

6. THIS CONTRACTOR IS REQUIRED TO MAINTAIN A MANUAL ON SITE CONTAINING THE REQUIRED MSDS SHEETS FOR PRODUCTS, CLEANERS AND OTHER MATERIALS USED ON THIS PROJECT. THE INFORMATION MAY BE GIVEN TO THE JOBSITE OFFICE FOR RECORDS AND REVIEW. THIS CONTRACTOR SHALL FURNISH TO THE JOBSITE SUPER-INTENDENT THE NAME OF HIS APPOINTED SAFETY OFFICER AND PHONE NUMBER FOR USE IN THE EVENT OF AN EMERGENCY.

7. THE H.V.A.C. EQUIPMENT SCHEDULE SHOWN ON THE H.V.A.C. PLAN IS INTENDED TO ESTABLISH THE TYPE AND QUALITY OF EQUIPMENT REQUESTED BY THE OWNER AND ENGINEER. EQUALS MAY BE USED IF BID AS A VOLUNTARY ALTERNATE. THIS CONTRACTOR IS REQUIRED TO MEET THE ESTABLISHED QUALITY IN ANY CASE, AND WILL BE REQUIRED TO PROVIDE SAME IF THE MATERIAL THEY USED IN THEIR PROPOSAL WAS NOT APPROVED PRIOR TO BIDDING OR IS VIEWED AFTER THE BIDDING NOT TO MEET THE QUALITY REQUIREMENT. IT IS THIS CONTRACTOR'S RESPONSIBILITY TO OBTAIN THE APPROVAL PRIOR TO BID OR RISK IF NOT APPROVED AFTERWARD.

8. THIS CONTRACTOR IS RESPONSIBLE FOR DAILY CLEAN-UP OF HIS DEBRIS AND MATERIAL ORGANIZATION TO KEEP THE JOB SITE NEAT IN APPEARANCE. A DUMPMSTER SHALL BE PROVIDED BY THE OWNER OR PROJECT MANAGER FOR THE H.V.A.C. CONTRACTOR'S USE. SHOULD THIS CONTRACTOR FAIL TO KEEP HIS TRADES WORK CLEAN FROM DEBRIS ACCUMULATION, THE JOB SITE SUPERINTENDENT WILL SEE THAT A FIRM OR PERSON WILL PERFORM THE CLEAN-UP AND HAVE THE EXPENSE BACK-CHARGED AGAINST THIS CONTRACTOR'S CONTRACT.

4. THIS CONTRACTOR SHALL CLEAN, TEST AND BALANCE THE EQUIPMENT AND SUCH DEVICES AS TO ASSURE THE OWNER OF A QUALITY INSTALLATION. THE WORK, ONCE ACCEPTED BY THE OWNER (OR OCCUPIED) SHALL BE GUARANTEED FOR A PERIOD OF ONE (1) YEAR AGAINST DEFECTS IN MATERIAL OR WORKMANSHIP. ANY MATERIAL OR INSTALLATION FOUND TO BE FAULTY OR IN NON-COMPLIANCE WITH THE CODES (EXCEPT FOR OWNER ABUSE) SHALL BE REPAIRED, REPLACED OR CORRECTED TO THE SATISFACTION OF THE ENGINEER/ OWNER AT NO ADDITIONAL COST TO THE OWNER. THE MECHANICAL CONTRACTOR SHALL COORDINATE EQUIPMENT HOOK-UP WITH.

10. THE PLUMBING CONTRACTOR TO INSURE PROPER SIZE AND DELIVERY PRESSURE OF NATURAL GAS TO EACH PIECE OF EQUIPMENT AND TO OVERALL SYSTEM REQUIREMENTS. REGULATORS, IF REQUIRED, TO BE FURNISHED AND INSTALLED BY THE MECHANICAL CONTRACTOR. NATURAL GAS PIPING AND EQUIPMENT SHUT-OFF GAS VALVES, DRIP LEGS ETC. TO BE FURNISHED AND INSTALLED BY THE PLUMBING CONTRACTOR.

11. UPON COMPLETION OF HIS RESPECTIVE WORK, THIS CONTRACTOR SHALL FURNISH OPERATING MANUALS, FIXTURE CUTS, CATALOG INFORMATION CONTAINING REPLACEMENT PARTS INFORMATION AND MAINTENANCE REQUIREMENTS, RECORD DRAWING INDICATING VARIATIONS FROM PLANS, AND 3 COPIES OF FIXTURE CUTS, MANUFACTURER, PRODUCT INFORMATION TO THE ENGINEER FOR PLACEMENT IN THE CLOSEOUT MAINTENANCE MANUAL.

12. ALL MATERIAL AND EQUIPMENT USED ON THIS PROJECT MUST COMPLY WITH ALL APPLICABLE STATE AND LOCAL CODE PROVISIONS. EQUIPMENT AND MATERIALS SHALL BEAR U.L., NEMA, AGA, OR ASME LABELS AND SATISFY THE REQUIREMENTS OF THE LOCAL UTILITY COMPANY AND GOVERNING AGENCIES.

1.3. THERMOSTATS FOR HEATING AND AIR-CONDITIONING EQUIPMENT TO BE FURNISHED BY THE H.V.A.C. CONTRACTOR. THE ELECTRICAL CONTRACTOR SHALL RUN THE CONTROL WIRING FROM THE THERMOSTAT TO THE EQUIPMENT, HOWEVER THIS CONTRACTOR IS RESPONSIBLE FOR VERIFYING THE PROPER INSTALLATION AND FOR THE FINAL CONNECTION TO THE MECHANICAL EQUIPMENT. THERMOSTATS SHALL BE OF THE TYPE THAT ALLOW BOTH AUTOMATIC AND MANUAL FAN OPERATION.

14. THIS CONTRACTOR SHALL PROVIDE FIRE DAMPERS AT REQUIRED OPENINGS, ALSO SHALL PROVIDE FOR THE PATCHING WHERE DUCTWORK OR EQUIPMENT PENETRATES FIRE WALLS OR FINISHED EXPOSED WALLS. FIRE STOP TAPES OR MATERIAL AS REQUIRED BY CODE SHALL BE THE RESPONSIBILITY OF THIS CONTRACTOR FOR HIS RESPECTIVE WORK.

15. THIS CONTRACTOR SHALL PROVIDE NECESSARY MATERIALS, DESIGN AND EQUIPMENT INSTALLATION TECHNIQUES AS TO QUIET UNNECESSARY NOISES DUE TO AIR VOLUME/VELOCITY, EQUIPMENT BLOWER FANS, EQUIPMENT VIBRATION ETC. THE SUPPORTS USED FOR EQUIPMENT SHALL BE DESIGNED IN SUCH A MANNER AS TO AVOID TRANSFER OF VIBRATION ONTO FLOORS, WALLS ETC. EQUIPMENT SUSPENSION METHODS AND MATERIALS MUST BE DESIGNED TO WITHSTAND REASONABLE POTENTIAL STRESSES, BASED UPON LOCATION AND INTENDED USE, WITH ACCEPTABLE SAFETY.

16. DUCTWORK, WHEN REQUIRED, SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE CURRENT SMACNA BULLETINS. ALL SUPPLY, RETURN, AND OUTSIDE AIR DUCTWORK SHALL BE INSULATED WITH ONE (1) INCH DUCTLINER GLUED AND GRIP NAILED ON 1'-0" CENTERS. OUTSIDE AIR SHALL BE SUPPLIED IN ACCORDANCE WITH STATE AND LOCAL CODES. ALL DUCTS TO BE EXTERNALLY INSULATED EXCEPT MAXIMUM 200 FEET MAY BE LINED IMMEDIATELY UPSTREAM/DOWNSTREAM OF AIR HANDLING UNITS FOR NOISE ATTENUATION. INTERNAL INSULATION FOR SUPPLY DUCTS AND OUTSIDE AIR DUCTS MUST BE GLOSS-CELL ELASTOMER. FIBERGLASS DUCT LINER IS NOT ALLOWED. VENTING OF GAS FIRED FURNACES SHALL BE IN ACCORDANCE WITH STATE AND LOCAL CODES. INSTALL THE PROPER TYPE VENT, FLASHING, COLLARS, AND CAPS AS REQUIRED FOR THE EQUIPMENT BEING INSTALLED.

17. REFER TO EQUIPMENT MANUFACTURER'S RECOMMENDED INSTALLATION INSTRUCTIONS FOR ALL REFRIGERATION LINES (ESPECIALLY THOSE EXCEEDING 50'-0" IN LENGTH). SUSPENDED PIPING IS TO BE SUPPORTED BY CLEVIS HANGERS AND SUITABLE STRUCTURAL CLAMPS OR MASONRY INSERTS. TRAPEZE HANGERS MAY BE USED WHERE APPROPRIATE. REFER LINES TO BE RUN CONCEALED IN WALL CAVITIES NOT EXPOSED ON OUTSIDE WALL.

18. ALL EXHAUST FANS, INCLUDING FAN-LIGHT COMBINATIONS, ARE TO BE FURNISHED AND INSTALLED BY THE H.V.A.C. CONTRACTOR. THIS SHALL INCLUDE DUCTING PER CODE TO THE EXTERIOR OF THE BUILDING. THE ELECTRICAL CONTRACTOR SHALL SUPPLY POWER AND CONNECT TO THE EXHAUST UNITS ONLY. WHERE REQUIRED ON THE PLAN, ROOMS HAVING GAS FIRED EQUIPMENT, (i.e. WATER)

19. HEATERS, FURNACES ETC.) SHALL HAVE SUFFICIENT COMBUSTION AIR TAKEN FROM THE BUILDING EXTERIOR, SUPPLIED IN THE AMOUNT OF OPENING REQUIRED BY THE GAS CO., STATE, & LOCAL CODE OFFICIALS. ALL LOUVERS SHALL BE FURNISHED AND INSTALLED BY THE H.V.A.C. CONTRACTOR. THIS CONTRACTOR SHALL FURNISH AND INSTALL ALL NECESSARY CONDENSATE DRAIN

20. LINES FROM THE EQUIPMENT TO A SUITABLE DRAIN LOCATION, PROPERLY SLOPE THE LINES FROM THE EQUIPMENT TO THE OUTLET. PROVIDE GALVANIZED METAL OR PLASTIC TRAY TYPE PANS UNDER EQUIPMENT LOCATED ABOVE THE CEILING OR FIRST FLOOR AS REQUIRED TO PREVENT POSSIBLE WATER MARKS ON FINISHED CEILINGS.

21. RELATED WORK TO BE PROVIDED BY OTHERS:

- a. POWER WIRING TO CONDENSERS, FURNACES, EXHAUST FANS, ...
- b. NATURAL GAS PIPING BY THE PLUMBING CONTRACTOR
- c. STAT WIRING FROM STAT TO MECH EQUIPMENT BY ELEC. CONTRACTOR

* Architects

MAUST
ARCHITECTURAL

SHEET SIZE 24x36

FT. WAYNE, INDIANA

REVISIONS

PRELIMINARY - NOT
FOR CONSTRUCTION

DATE: 05/01/20

JOB NO.: MAS-26-105

NAME: _____

MECHANICAL NOTES

SHEET

M003